



Sewerage Mainline Extension at Male' – PS04

Qualification of Bidders:

The bid document shall comprise the following information in the given format and order, which MWSC shall use to determine whether the Bidder possesses relevant experience, technical capacity to undertake the project works and to complete successfully in accordance with the bid. Any bid did not accompanied by the following in the given **format and order** shall be rejected by the Employer as non-responsive.

- Bid form. Must be filled stamped and signed. Amount stated in the bid document should be exclusive of GST and should tally with the amount stated in the BOQ.
- Bid Security (10,000/-)
- MIRA tax clearance (within 06 months). Must be clear.
- MNPHI Contractors Registration Certificate
- Business Registration Certificate at Economic Ministry
- Company Business Information Sheet (Economic Ministry), generated within 1 month prior to the Bid submission deadline
- GST Registration
- Priced BOQ. Must be filled and complete. BOQ should not be altered. Bidder's rates should not be more than two decimals.
- Work schedule. Should tally with the duration stated in Bid form
- Site Organization chart
- Resource allocation proposed for the project in the given format "Resource allocation plan" under Section II - Sample Tendering Forms
- Experience – Part 1 list of Similar Projects completed over last five years in the given format "Form of Experience" under Section II - Sample Tendering Forms
- Experience – Part 2 list of Ongoing MWSC Projects in the given format "Form of Experience" under Section II - Sample Tendering Forms. (Applicable for bidders with ongoing contract commitments with MWSC)

Scope of Works

1. Location of the Works

The site for the works proposed under this contract is at Male', Izzuddeen Magu, Sabudheli Magu and Buru Magu, Maldives.

2. Description of the Works.

The contract work constitutes the following:

1. Site Management costs.
2. Conduct Survey to check locations of manholes and existing ground level prior to work
3. Transportation of materials and equipment's to site and labour works.
4. Excavation and backfilling, compaction works.
5. Shoring and Dewatering works.
6. Excavation of trench for UPVC sewer network for **MH-41 To MH 37,** (depth 0.8 - 1.3) laying of parallel lines (160mm Dia) as per the drawing, testing, laying of warning tape on the pipes, back filling and compaction.
7. Excavation of trench for UPVC sewer network for **MH 529 to PS 4,** (depth 1.65 - 1.7) laying of parallel (200mm Dia) lines as per the drawing, testing, laying of warning tape on the pipes, back filling and compaction.
8. Core drilling of existing manhole chamber for connection to new sewer mainline and proper sealing of pipe entry points with approved methods.
9. Fiber coating to internal surfaces of manholes including surface preparation and curing of these manholes after sewer line connection
10. Reinstate the work area to its original condition upon completion of work.
11. Providing as-built drawings and supporting technical specification documents upon completion.

NOTE:

1. Contractor is responsible to obtain relevant permits from appropriate agencies. Work schedule should include the required durations.
2. The contractor shall supply the as-built drawing within fifteen days after completion of the project.
3. The contractor is responsible for surveying the condition of the working site.
4. MWSC can assist contractors in communicating with relevant authorities.

