ދާއިރە ވެސްކަން ކުރުމުގެ ދިވެހިރާજ ފަރާތް

Providing Labor and Equipment Services for the Construction of Sewerage Pumping Stations at B. Dhonfanu

Qualification of Bidders:

The bid document shall comprise the following information in the given format and order, which MWSC shall use to determine whether the Bidder possesses relevant experience, technical capacity to undertake the project works and to complete successfully in accordance to the bid. Any bid did not accompanied by the following in the given **format and order** shall be rejected by the Employer as non-responsive.

- Bid form. Must be filled stamped and signed. Amount stated in the bid document should be exclusive of GST and should tally with the amount stated in the BOQ.
- Form of Declaration of No Conflict of Interest & Ethical Conduct
- Bid Security
- MIRA tax clearance (within 06 months). Must be clear.
- MNPHI Contractors Registration Certificate
- Business Registration Certificate at Economic Ministry
- Company Business Information Sheet (Economic Ministry), Generated within 1 month prior to the Bid submission deadline
- GST Registration
- Priced BOQ. Must be filled and complete. BOQ should not be altered. Bidder's rates should not be more than two decimals.
- Work schedule. Should tally with the duration stated in Bid form
- Site Organization chart
- Resource allocation proposed for the project in the given format "Resource allocation plan" under Section II - Sample Tendering Forms
- Experience – Part 1 list of Similar Projects completed over last five years in the given format "Form of Experience" under Section II - Sample Tendering Forms
- Experience – Part 2 list of Ongoing MWSC Projects in the given format "Form of Experience" under Section II - Sample Tendering Forms. (Applicable for bidders with ongoing contract commitments with MWSC)

Scope of Works

1. **Location of the Works**

The site for the works proposed under this contract is in the Island of **B. Dhonfanu.**

2. Description of the Works

The contract work constitutes the following:

a) Site clearing & leveling for execution of the works.
b) Construction of Sewer Pump Stations as per drawing and specification.
   - Construction of RCC sewage collecting Sump well
   - Construction of Valve chambers
   - Construction of Pump Panel shelters
   - Construction of PS site boundary fence
   - Construction of Vent stack
   - Construction of Light post
   - Construction of sampling pit (well)
c) Site cleaning upon completion.
d) Providing As-built Drawings & supporting technical specification documents upon completion.

NOTE:

1. **All the items on the bills are for supplying and construction unless otherwise specified.**
2. **Item rate shall include for all scaffolding works, shoring, and as such as required for laying of the pipe.**
3. **Unless otherwise specified all pipes, fittings, network gate valves and washout valves and marker tape will be provided by the Employer.**
4. **Unless otherwise specified all sewer network pipes, fittings, plastic manholes, inspection chambers, cast iron manhole covers and frames will be provided by the Employer.**
5. **All butt weld jointing of the sea outfall pipeline will be carried out by MWSC. Contractor shall arrange the electricity/Generator for butt welding works (5KV electric output)**
6. **All SS316L Grade items required for the Brine Outfall will be provided by MWSC.**
7. **Contractor shall clear the site of excavation if required (including bushes and tree cutting). MWSC will pay for compensation for the trees to the required authority if needed.**
8. **Excavations should be done with safety measures like proper care and shoring for the structures and their boundaries. The contractor should be responsible for proper safeguards for the nearby structures.**
9. **The contractor is responsible for any damage to the existing building property during construction. The contractor shall indemnify the respective party against all losses or claims.**

10. **SRC shall be used for the brine well, rainwater lift well, sewer pump station sump well, valve chamber, and outfall anchor blocks. Normal Portland cement can be used for other structures.**
11. **The contractor should arrange transportation and storage facilities for all the materials.**
12. **The rate shall include dewatering and disposal of water according to site conditions/away from existing building areas. (The contractor is to discuss and negotiate with the Island authorities regarding the location and a proper method of dewatering.)**
13. **Dewatering should be done according to the rules and regulations and the ERA guideline.**
14. **Leak test should be carried out according to the specification. All the testing equipment should be arranged by the contractor. Upon leak testing by MWSC, if a leak is found to be due to default of the contractor, the contractor shall carry out the labour work for rectification. But if the leak is due to an issue not from the contractor, the contractor shall not be responsible for rectification.**
15. **Clear groundwater mixed with chlorine shall be used for pipe cleaning.**
16. **It is the responsibility of the contractor to check on site and any matter of concern, such as the width of roads, before quoting.**
17. **Contractor shall supply the 'as-built' drawing within 15 days after the completion date.**
18. **All tests should be carried out according to the specification. All the testing equipment should be arranged by the contractor.**
19. **Contractor has to arrange water and electricity**
20. **All the items on the bills are for supply and construction unless otherwise specified.**

Summary of evaluation criteria with weights

Part - A

#	Criteria	Weighting %
1	Resource	Pass/Fail

Part - B

#	Criteria	Capability
1	Price	85%
2	Experience	10%
3	Local Preference	5%